

SBS Details: D1.7.2-3 Parapets & Copings (High Parapet – Supported)



Notice to reader: Drawing for illustration purposes only. Consult the RoofStar Guarantee Standards for more information.

1 WORK INCLUDED

(1) [Gypsum Deck Overlay](#)

If required by design authority.

(2) [Vapour Retarder](#)

If required by design authority.

(3) [Insulation](#)

See available insulation products in the [Accepted Materials](#) section of this Manual.

(4) [Insulation Overlay Board](#)

As required.

(5) [Primary Membrane and Membrane Protection](#)

(6) [Base Sheet Flashing](#)

Mechanically fasten to parapet at termination.

(7) [Base Metal Flashing](#)

Optional on flexible membrane systems. Required on assemblies using gravel ballast filter mats. See **Section 13.6 - Cap Flashings, Base Flashings and Reglets.**

(8) [Metal Counter Flashing](#)

Minimum 250 mm (10") above roof surface.

(9) [Metal Cap Flashing](#)

Required whenever the primary roof membrane flashing/stripping is carried over the top of parapet walls. See **Section 13.6 - Cap Flashings, Base Flashings and Reglets.**

2 RELATED WORK BY OTHERS

(A) [Acceptable Deck](#)

(B) **Air / Vapour Seal**

(C) [Acceptable Wall Surface](#)

(D) **Wood Blocking**

(E) [Sloped Wood Blocking](#)

Required over 100 mm (4") parapet width.

(F) [Wall Sheathing Membrane](#)

Minimum 1 mm (0.040") self-adhered modified bitumen.

(G) **Exterior Wall Finish**

(H) [Metal Cap Flashing](#)

Required by others whenever the primary roof membrane is not carried over top of the parapet and/or when the wall finish is by others. (Unless specified otherwise).

(I) [Cap Flashing Underlay](#)

Minimum 1 mm (0.040" or 40 mil) self-adhered modified bitumen.